Computation of Limiting Overheating and Thermal Impairing (Cont.) constant rated load); kf = $\frac{Se}{Sav}$ curve form factor; $\beta = \frac{Sav}{Sr}$ - average duty factor of the transformer, where S_c - mean quadratic load; S_{av} - average load as

plotted on a daily graph; S_r - rated power of transformer. The nomogram permits the following general conclusions to be drawn. 1. The most important factor in selecting transformer power is the thermal impairing of the insulation, not the limiting heating up temperature. 2. Insulation impairing close to the natural wear with a variable load can be obtained if temperature rises above the rated (105°) are permitted. 3. An increase in k_f and \(\int)\) greatly increases the thermal impairing. The nomogram and load chart can be used for finding the degree of thermal impairing of transformer insulation, and for selecting transformer power on the basis of a definite thermal impairing factor of insulation.

ASSOCIATION: Novocherkassk Polytechnical Institute (Novocherkas. politekhn. in-t)

Card 2/2

APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0"

Knynloo, 6 m. GITEL'SON, S.H.; KAYALOV, G.M. Economic evaluation of methods of increasing cos in industrial plants. Energ. biul. no.5:15-18 My '57. (MIRA 10:6

KAYALOV, G.M.

On S.A. Kudriashov's remarks. Energ. biul. no.5:21-22 My '57. (Electric power) (Kudriashov, S.A.) (MIRA 10:6)

AUTHOR:

Kayalov, G.M.

SOV/90-58-1-1/9

TITLE:

On Calculating the Reactive Electric Power Needed by Industrial Electric Motors (K raschëtu potrebleniya reaktivnoy

elektroenergii promyshlennymi elektroprivodami)

PERIODICAL:

Energeticheskiy byulleten', 1958, Nr 1, pp 1-4 (USSR)

ABSTRACT:

Difficulties arise in the designing of industrial-plant electric equipment and in the mising of the power factor. These difficulties concern the calculation of reactive electric power consumption. Experimental determination of the amounts of reactive electric power needed by basic consumers (asynchronous motors) also faces some difficulties. The author therefore gives a formula which expresses the interdependence between the reactive-power utilization factor on the one hand, and the switch-in factor as well as the active-power utilization factor on the other. He also gives another variant of the same formula, applicable to an entire line of motors. At the end he derives formulas applicable for calculating the average power factor of asynchronous motors in

Card 1/2

SOV/90-58-1-1/9

On Calculating the Reactive Electric Power Needed by Industrial Electric Motors

correlation with switch-in factors and active-power utilization coefficients.

There is 1 table and 3 Soviet references.

Card 2/2

"APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0

KayaLov, G.M.

94-1-15/24

AUTHOR: Kayalov, G.M., Candidate of Technical Sciences

TITIE: On a Scale of Standard Voltages for Industrial Distribution Systems and Electrical Equipment (O shkale standartnykh napryazheniy dlya promyshlennykh elektrosetey i priyemnikov)

PERIODICAL: Promyshlennaya Energetika, 1958, , No.1, pp. 31 - 33 (USSR)

**ABSTRACT: This is a discussion of an article by Yu.L. Mukoseyev "Promyshlennost' trebuyet napryazheniya 660/380 V" - Promyshlennaya Energetika, 1956, No.8. The desirability of a standard distribution voltage of 15 kV was discussed in 1947 by
G.V. Serbinovskiy and Yu.N. Baskakov (Elektrichestvo, 1947,
No.1). The author then argues the merits and demerits of 35 kV
as an industrial distribution voltage and considers that it is
too high except for a few special cases where very large loadings
are involved. However, the next standard voltage, 10 kV, is
often inconveniently low. More attention should be paid to the
possibility of using 15 kV for industrial distribution. The
value of 660 V recommended for supply to large equipment (above
100 kW) is not a good one. It would be better to use the
standard voltages of 3 or 6 kV. A number of other remarks are
made about the selection of voltage for industrial distribution.
There is an editorial note than an expet commission of the
Cardl/2

94-1-15/24
On a Scale of Standard Voltages for Industrial Distribution Systems and Electrical Equipment

Committee of Standards, Weights and Measuring Instruments examined the draft standard "Rated Voltages for Electric Power Systems and Connected Equipment" and recommended the inclusion of a voltage of 21 kV for generators (instead of 15 kV) in order to be able to supply directly a number of large urban and industrial loads without transformers. It was also recommended to include the voltage of 660 V to meet the needs of the mining industry.

ASSOCIATION:

Novocherkassk Polytechnical Institute (Novocherkasskiy

politekhnicheskiy institut)

AVAILABLE:

Library of Congress

Card 2/2

APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0"

"APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0

KAYALOV, Georgiv Mikhaylovich, kand. tekhn. nauk, dots.

Load of electric networks used for mass and automatized production. Izv. vys. ucheb. zav.; elektromekh. 1 no.6:108-114 58.

(MIRA 11:9)

1. Kafedra elektrifikatsii promyshlennykh predpriyatiy Novocherkasskogo politekhnicheskogo instituta. (Electric networks)

SOV/112-59-5-8888

8(3)

Translation from: Referativnyy zhurnal, Elektrotekhnika, 1959, Nr 5,

PP 66-67 (USSR)

AUTHOR: Kayalov, G. M.

TITLE: Using the Probability Theory in the Analysis of Industrial Loads

PERIODICAL: Izv. vyssh. uchebn. zavedeniy. Elektromekhanika, 1958, Nr 1,

ABSTRACT: Direct calculation of load is necessary for fairly large receivers; however, it is unsuitable in evaluating a mass of receivers. For the latter case, using the probability theory and mathematical statistics is expedient at all stages of load-calculation procedure: (1) investigating existing relationships; (2) developing design formulae; (3) deriving the numerical data that would determine the design load from experimental data. The contradiction between the complicated initial physical relationships and the required simplicity of mass calculations necessitates a certain compromise in the final

Card 1/3

Novocherkassky Polytech. Inst.

SOV/112-59-5-8888

Using the Probability Theory in the Analysis of Industrial Loads

correlation function
$$B(\tau) = \lim_{T\to\infty} \frac{1}{T} \int_{0}^{T} P(t)P(t+\tau)dt$$
. The latter shifted in time 1.

provides a numerical evaluation of the correlation between the load curve values shifted in time by any stretch C= const. It is essential that Bo = P2. $B(\infty) = P^2$, where Pe and Psr are the effective and average values of the load. The expressions $B(\mathcal{T})$ for the simplest single-receiver curves and for the total load curve are given. Sample curves for which P Omax varies on a nonmonotonic pattern with the increase of Θ are presented; however, the dispersion of the random value Po decreases always monotonically. Bibliography: 8 items.

G.M.K.

Card 3/3

KAYALOV, Georgiy Mikhaylovich, kand, tekhn, nank, dots.

Calculated value of load variations in industrial electric networks. Inv. ws. ucheb. mav.; elektromakh. 1 no.3:123-129 '58. (MIRA 11:6)

l. Kafedra elektrifikatsii promyshlennykh predpriyatiy Novocherkasskogo politekhnicheskogo instituta. (Electric networks)

KHIM~01, 611.

AUTHOR:

Kayalov, G.M.

90-58-4-3/6

TITLE:

Economic Solutions to the Supplying of Industrial Plants With Electric Power (Ob ekonomicheskikh resheniyakh v elektrosnabzhenii promyshlennykh predpriyatiy)

PERIODICAL:

Energeticheskiy Byulleten', 1958, Nr 4, pp 21-28 (USSR)

ABSTRACT:

Calculations of the costs of supplying industrial plants with electricity are mostly based on operation costs, amortization, etc. In the article the different factors determining such calculations are discussed. An important economic factor is the initial capital investment of any electric current supply system. The problem of correlating the initial and current expenditures is not yet completely solved. The opening of new coal mines belongs also to the initial capital investment. The specific initial investment regarding electric power stations alone amounts to 1,200 - 3,000 rubels per kw. The investment regarding the opening of coal mines is approximately 490 rubels per kw. The amortization deductions are a part of the current expenditures and give no return. It is important to know, if the initial capital investment should be kept low although the current expenditures are later increased by this

Card 1/3

<mark>indentalingudental</mark>esetationesetata discontantición (etc. 18 de l'encludadad esta <mark>esta discultantalingu</mark>al esta e

90-58-4-3/6

Economic Solutions to the Supplying of Industrial Plants With Electric

method; or if the initial investment should be high so that the current expenditures may be kept low. These considerations are influenced by the amortization term which must be determined separately in every case. In the Soviet Union, an important role is played by the factor of socialist accumulation; for the calculation of this formulas are given. It is admitted that there are often differences between the actual costs of the final product, raw materials, etc., and the costs determined by the price lists. If the reliability and the steadiness of operation of different systems is the same, it remains to be considered in which system the energy losses and the need of nonferrous metals is lowest. It is expedient to choose a solution which involves a somewhat increased current expenditure, to save a greater quantity of nonferrous metals. In comparison to municipal power lines, the industrial lines have a load limit which is easily reached; they are not very long and auxiliary lines may be laid without much expenditure when needed; the loss of voltage is low. The increase of the cross section of these lines beyond minimum

Card 2/3

90-58-4-3/6

Economic Solutions to the Supplying of Industrial Plants With Electric Power

requirements is admissible only if there are concrete economic reasons for it. The distribution of a certain quantity of monferrous metals between several power lines should be made according to their economic cross sections without regard to their length.

There are 14 Soviet references.

AVAILABLE:

Library of Congress

Card 3/3

1. Electrical systems-Economic aspects

KAYALOV, Georiy Mikhaylovich, dotsent, kand.tekhn.nauk

Determining the effective number of receivers in calculations of industrial electric networks. Isv.vys.ucheb.sav.; elektro-mekh. 3 no.1:120-125 60. (MIRA 13:5)

1. Kafedra elektrifikatsii promyshlennykh predpriyatiy Novocherkasskogo politekhnicheskogo instituta. (Electric networks)

KAYAIOV, Georgiy Mikhaylovich, kand. tekhn. nauk, dotsent

Rational scientific methods based on three present-day techniques for the approximate integration of equations in the theory of automatic control. Izv. vys. ucheb. sav.; elektromekh. 3 no.3: 140-143 60. (MIRA 13:10)

l. Kafedra elektrifikatsii promyshlennykh predpriyatiy Novocherkasskogo politekhnicheskogo instituta. (Automatic control) (Calculus, Operational)

AVILOV-KARNAUKHOV, Boris Nikolayevich, doktor tekhn.nauk, prof.; KAYALOV,

Georgiy Mikhaylovich, kand.tekhn.nauk, dotsent; ERUSENTSOV,

Leonig Vasil'yevich, assistent; SHALYGIN, Igor'Vladimirovich,
assistent

Pevices for studying the long-term processes. Izv. vys. ucheb. zav.; elektromkh. 3 no.7:92-98 '60. (MIRA 13:9)

1. Zaveduyushchiy kafedroy elektrifikatsii promyshlennykh predpriyatiy Novocherkasskogo politekhnicheskogo institut (for Avilov-Karnaukhov). 2. Novocherkasskiy politekhnicheskiy institut (for Kayalov). 3. Kafedra elektrifikatsii promshlennykh predpriyatiy Novocherkasskogo politekhnicheskogo institut (for Brusentsov). 4. Kafedra elektrifikatsii promyshlennykh predpriyatiy Novocherkasskogo politekhnicheskogo institut (for Shalygin). (Recording instruments)

5/144/60/000/05/012/014 E194/E255

Kayalov, G. M., Candidate of Technical Sciences, and Brusentsov, L. V AUTHORS:

Brusentsov, I. V

Correlation Functions of Load Curves of the Electrical

Correlation Functions of Load Their Practical Significance

Drives of Machine Tools and Their Practical Significance

TITIE:

: Izvestiya vysshikh uchebnykh zavedeniy Elektromekhanika, 1960, Nr 5, pp 123-129 (USSR) PERIODICAL:

ABSTRACT: The meaning of the term "correlation function" is first defined; it is a limit of the form given by expression defined; it is a limit of the form widely used (1). Correlation functions are becoming widely used for a variety of purposes, including analysis and calculation of the loads on industrial electrical systems. The correlation function gives the variation of possible mean values of load over a given time interval. Thus if the correlation function of the load curve is known, the statistical three sigma rule may be used to calculate maximum loads of any duration, such as half an hour or fifteen minutes. Moreover, knowledge of the correlation function of load curves of individual current-consuming devices is very useful for assessing whether the manufacturing process is sufficiently

card 1/6

8/144/60/000/05/012/014 E194/E255

Correlation Functions of Load Curves of the Electrical Drives of Machine Tools and Their Practical Significance

The present article considers rhythmic and organised. both these applications of the correlation function. Hitherto, the correlation functions of load curves of industrial electric power systems have not been studied experimentally: the authors describe such a study carried out in the machine shops of an Electric Locomotive Works and of a Tractor Works. The measurements in the shops were carried out by a student A. Derevyanchenko and Engineer S. Pronin. Determination of each individual point on the curve of the correlation function requires laborious integration and the work was greatly facilitated by the use of two special semiautomatic measuring instruments designed by one of the present authors. These instruments, a recorder and an analyser, were described in Izvestiya vysshikh uchebnykh zavedeniy, Elektromekhanika, Nr 8, 1958. The recorder was used to determine the load curves in the form of special photographs and the analyser was used as a correlator to make automatic calculations of the right-Card 2/6 hand side of formula (1). In practice, the infinite

\$/144/60/000/05/012/014 E194/E255

Correlation Functions of Load Curves of the Electrical Drives of Machine Tools and Their Practical Significance

limits of integration given in formula (1) must be replaced by finite limits. Figs la and 3a give typical examples of correlation function curves for the individual load curves of machine tools determined in this way. If the machine is running rhythmically, that is, if the load curve is strictly periodic, the correlation function is also periodic. In practice, this applies only to automatic machines: in other cases the duration of the operating cycle varies in a random manner from one cycle to the next. Therefore, the correlation function of the individual load curve is no longer periodic but ranges between the rms and the mean ordinates of the load curve during the shift. Figs 1b and 3b give curves of the distribution of the duration of an individual cycle obtained directly from the load curves of individual machines. The actual load curves are not given because their shape during a single cycle of the machine tool does not influence the damping time of the correlation Card 3/6 function curve. It will be seen that the graph of Fig la,

s/144/60/000/05/012/014 E194/E255

Correlation Functions of Load Curves of the Electrical Drives of Machine Tools and Their Practical Significance

which corresponds to a relatively small dispersion in the value of the cycle time (see Fig 1b) has the most nearly periodic correlation function. A summated effect arises from the super-position on a strictly periodic but weak signal of stronger irregular interference. graphs of the correlation functions are constructed, they can be used to reveal the presence of the signal and to determine its periodicity from the periodicity of the damped wave of the correlation function. This principle may be used to detect machine stoppages in the common case when the dispersion is relatively great and the stops are relatively small. Under such conditions, it is difficult to establish the presence and duration of stops directly from the load curve and the indirect method is to be preferred. First the mean value of the duration of the cycle is determined. It corresponds to the required normal law on a load curve without stoppages, and suffices to determine the period of damped waves on the correlation function graph. Then, on the experimental Card 4/6 distribution curve, experimental values of the cycle time

S/144/60/000/05/012/014

Correlation Functions of Load Curves of the Electrical Drives of Machine Tools and Their Practical Significance

are laid off from the origin to determine the mean value of the standing time. It has been found that variations in the cycle time depend almost entirely on variations in the stopping time, whilst the time which the machines are in operation is usually constant. This has been observed in many workshops and it also applies to the load curves of underground sub-stations in coal mines. Fig 4 shows the correlation function of a feeder load curve which is aperiodic, whilst that in Fig 5 contains a damped periodic oscillation associated with the presence in the load of one large item of current-consuming apparatus. In general, the presence of damped waves in the graph of the correlation function of the total load of a group of power-consuming equipment has no important influence on the dispersion of the mean loads over particular intervals of time. If there are waves in the graph the envelopes of the maxima and minima may have different time-constants, as may be seen in the graphs of Figs 3a and 5. Attempts by the authors to obtain a simple graphical experimental relationship between the time

Card 5/6

S/144/60/000/05/012/014 E194/E255

Correlation Functions of Load Curves of the Electrical Drives of Machine Tools and Their Practical Significance

constant of damping of the correlation relationships and other constants was unsuccessful; but in no case did the ratio of this time constant to the cycle time exceed 4, so that expression (5) was generally valid. The method of using the data obtained in the present power systems falls outside the scope of the present article. There are 5 figures and 6 Soviet references.

ASSOCIATION: Novocherkasskiy politekhnicheskiy institut (Novocherkassk Polytechnical Institute)

SUBMITTED: January 28, 1960

Card 6/6

C KAYALOV, G.M.

Principles of constructing the electric networks of industrial enterprises in the U.S.S.R. !Izv. vys. ucheb. zav.; elektromekh. 4 no. 1:100-112 '61. (MIRA 14:4) (Electric power distribution)

KAYALOV, Georgiy Mikhaylovich, kand tekin nauk, dotsent

Rated load of the feeder of an electric network and a method for calculating it for a given graph. Izv. vys. ucheb. zav.; elektrometh. 4 no.4:114:131 '61. (MIRA 14:7)

1. Kafedra elektrifikatsii promyshlennykh predpriyatiy Novemerkasskogo politekhnicheskogo instituta. (Electric power distribution)

KAYALOV, Georgiy Mikhaylovich, kand.gekhn.nauk, dotsent

Theory of random processes and calculation of the loads of industrial electric networks. Izv. vys. ucheb. zav.; elektromekh. 4 no.12: 13-21 '61. (MIRA 15:1)

l. Kafedra elektrifikatsii promyshlennykh predpriyatiy Novocherkasskogo politekhnicheskogo instituta. (Electric power distribution)

KAYALOV, GEORGIY MIKHAYLOVICH, kand.tekhn.nauk, dotsent

Theory of random processes and calculation of the loads of electrical networks of factories. Izv. vys. ucheb. zav.; elektromekh. 4 no.11:65-81 '61. (MIRA 14:12)

1. Kafedra elektrifikatsii promyshlennykh predpriyatiy Novocherkasskogo politekhnicheskogo instituta. (Electric networks) (Electric power distribution)

VOLOBRINSKIY, S.D.; GRODSKIY, S.Ye.; YERMILOV, A.A.;

KAYALOV, G.M.; LIVSHITS, D.S.; MAKSIMOV, A.A.; MESHEL',

B.S.; MUKOSEYEV, Yu.L.; OGORODNOV, S.I.; ROZENBERG, V.A.;

SHRAYBER, L.G.; ZALESSKIY, Yu.Ye., retsenzent; IOKHVIDOV,

E.S., retsenzent; FEDOROV, A.A., retsenzent; SAVEL'YEV,

V.I., red.; LARIONOV, G.Ye., tekhn. red.

[Temporary instructions for determining the electrical loads of industrial enterprises] Vremennye rukovodiashchie ukazania po opredeleniiu elektricheskikh nagruzok promyshlennykh predpriiatii. Moskva, Gosenergoizdat, 1962. 45 p.

(MIRA 16:2)

1. Russia (1923- U.S.S.R.) Glavnoye energeticheskoye upravleniye. 2. Leningradskoye otdeleniye Gosudarstvennogo proyektnogo instituta tyazheloy promyshlennosti (for Kizevetter,
Kleyn, Kharchev). 3. Komissiya po elektricheskim nagruzkam
Nauchno-tekhnicheskogo obshchestva energeticheskoy promyshlennosti (for Volobrinskiy, Grodskiy, Yermilov, Kayalov, Livshits,
Maksimov, Meshel, Mukoseyev, Ogorodnov, Rozenberg, Shrayber).

(Electric power distribution)

KAYALOV, G.M., kand. tekhn. nauk

Calculation of electrical loads of industrial enterprises. Prom. energ. 18 no.12:38-39 D '63. (MIRA 17:1)

VOLOBRINSKIY, Sergey Davidovich; <u>KAYALOV</u>, <u>Georgiy Mikhaylovich</u>; KLEYN, Petr Nikolnyevich; <u>MESHEL</u>, Boris <u>Solomonovich</u>; SYROMYATNIKOV, I.A., prof., retsenzent; KNYAZEVSKIY, B.A., dots., retsenzent; <u>GRODSKIY</u>, S.Ye., red.

[Electrical loads of industrial enterprises] Elektricheskie nagruzki promyshlennykh pred miatii. [By] S.D.Volobrinskii i dr. Moskva, Izd-vo "Energiia," 1964. 303 p. (MIRA 17:8)

"APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0

KAYALOV, Georgiy Mikhaylovich, kand.tekhn.nauk, dotsent

Principle of the maximum mean load in the calculation of electrical networks. Izv.vys.ucheb.zav.; elektromekh. 7 no. 3: 367-374 164. (MIRA 17:5)

1. Kafedra elektrifikatsii promyshlennykh predpriyatiy Novecherkasskogo politekhnicheskogo instituta.

AVILOV-KARNAUKHOV, B.N.; BOGUSH, A.G.; BOLYAYEV, I.P.; GIHIS, A.F.; DROZDOV, A.D.; KAYALOV. G.M.; MIRONOV, Ye.P.; MIKHAYLOV, D.I.; SEKRETEV, D.I.; SINEL'NIKOV, Ye.M.; CHERNYAVSKIY, F.I.

An cutstanding scientist; on professor A.G.Beliavskii's 80th birthday. Jzv.vys.ucheb.zav.; elektromekh. 7 no.11:1399-1400 (MIRA 18:3)

OGORODNOV, S.I., inzh.; KAYALOV, G.M., doktor tekhn. nauk; GRODSKIY, S.Ye., inzh.; VOLOBRINSKIY, S.D., kand. tekhn. nauk

Methods for calculating the electrical loads of industrial enterprises. Prom. energ. 20 no.5:33-42 My '65. (MIRA 18:7)

1. Gor'kovskiy avtomobil'nyy zavod (for Ogorodnov). 2. Novocherkasskiy politekhnicheskiy institut (for Kayalov). 3. Gosudarstvennyy institut po proyektirovaniyu traktornoy promyshlennosti i sel'skokhozyaystvennogo mashinostroyeniya (for Grodskiy).

KAYALOV, Georgiy Mikhaylovich, doktor tekhn. nauk, prof.; KURENNYY, Eduard Grigor'yevich, aspirant

Experimental determination of the statistical indexes of electric load graphs. Izv. vys. ucheb. zav.; elektromekh. 8 no.1:95-101 165.

(MIRA 18:3)

1. Kafedra elektrifikatsii promyshlennykh predpriyatiy.

"APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0

VOLOBRINSKIY, S.D.; KAYALOV, G.M.; KLEYN, P.N.

Raply to D.S.Livehita's remarks on the discussion or the methodology for determining the Logis of Industrial electrical distribution networks of plants. Elektrichestvo no.5188-89 My '65.

(MIRA 18:6)

KAYALOV, Georgiy Mikhaylovich, doktor tekhn.nauk; KUREMNYY, Eduard Grigor'yevich, aspirant

Use of the queueing theory in calculating peak loads of industrial electric power distribution networks. Izv.vys.ucheb.zav.; elektromekh. 8 no.7:803-815 '65. (MIRA 18:8)

1. Rostovskiy institut inzhenerov zheleznodorezhnogo transporta (for Kayalov). 2. Kafedra elektrooborudovaniya promyshlennykh predpriyatiy Novocherkasskogo politekhnicheskogo instituta (for Kurennyy).

RAYALOV. G.M., doktor tekhn.nauk, prof.

Bibliography. Elektrichestvo no.10:93-94 0 '65.

(MIRA 18:10)

AVILOV-KARNAUKHOV, B.N.; BATURO, V.I.; BAKHVALOV, Yu.A.; BOGUSH, A.G.;
BOLYAYEV, I.P.; GIKIS, A.F.; DROZDOV, A.D.; KAYALOV, G.M.; KLEYMENOV,
V.V.; KOLESNIKOV, E.V.; MALOV, D.I.

Professor Efim Markovich Sinel'nikov, 1905-; on his 60th birthday. Elektrichestvo no.9:89 S 65.

(MIRA 18:10)


L 22425-66 ENT CC NR. A16013623 ENT(3)/EWP(K)/EWP(1) SOURCE CODE: UR/0105/65/000/009/0089/0090 AUTHOR: Avilov-Karnaukhov, B. N.; Baturo, V. I.; Bakhvalov, Yu. A.; Bogush, A. G.; Bolyayev, I. P.; Gikis, A. F.; Drozdov, A. D.; Kayalov, G. M.; Kleymenov, V. V.; Kolesnikov, E. V.; Malov, D. I. ORG: none TITLE: Honoring the 60th birthday of Professor Yefim Markovich Sinel'nikov SOURCE: Elektrichestvo, no. 9, 1965, 89-90 TOPIC TAGS: academic personnel, electric engineering personnel, computer research Professor Sinel'nikov was born 11 May 1905 in Yekaterinoslav (now Dnepropetrovsk) in the family of a clerk. Following his graduation from the Khar'kov Electrical Engineering Institute in 1930 he was appointed chief of the Tochnical Division on Electric Drive at the Khar'kov Electrical Machinery Plant. Subscquently he was appointed research engineer at the Vol'ta Plant and later on transferred to Moscow, to the Institute of Experimental Medicine, while at the same time he continued his studies. In 1946 he started working as a senior scientific researcher at the All-Union Electrical Engineering Institute. Since September 1953 Professor Sinel'nikov has been working at the Novocherkassk Polytechnic Institute. At present he is head of the Chair of Card 1/2 UDC: 621,313


L 22425-66 ACC NR: AP6013623


Electrical Machinery, Apparatus, and Computers and Mathematical Devices. He has been instrumental in establishing the computer laboratory at this institute, where research is being performed on the problems of utilizing computer engineering in the design and calculation of electromagnetic, mechanical, and thermal processes in electrical machinery and equipment. Since 1958 Professor Sinel'nikov has been Coordinating Editor of the journal Elektromechanika (Electromechanics) - one of the series published under the aegis of Izvestiya Vysshikh Uchebnykh Zavedeniy (News of Higher Schools). Yefim Markovich is moreover a prominent educator and the holder of many social honors and consultant to a series of industrial enterprises. For his great merits as an educator and for his scientific contributions he has been awarded the Order of Labor Red Banner. Orig. art. has: 1 figure. [JPRS]

SUB CODE: 09 / SUBM .DATE: none

Cord 2/2///







APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0"

AUTHORS:

Tokareva, A. V., Bergman, A. G.,

307/78-3-9-31/48

Kayalova, J. S.

TITLE:

Reciprocal System of Nitrates and Chlorides of Sodium and Calcium (Vzaimnaya sistema iz nitratov i khloridov natriya

i kal'tsiya)

PERIODICAL:

Zhurnal neorganicheskoy khimii, 1958, Vol. 3, Nr 8,

pp. 1909-1913 (USSR)

ABSTRACT:

Details were given of the experimental examinations of the reciprocal system of nitrates and chlorides of sodium and calcium in the presence of solvents. These examinations were performed by means of visual-polythermal methods. The system Na, Ca \parallel Cl, NC₃ is comparatively simple and the components

forming the system do not react with each other by forming complex compounds and solid solutions. This system is analogous to the systems: Na, Sr \parallel Cl, NO₃ and Na, Ba \parallel Cl, NO₃.

The results demonstrate that the reciprocal system

Na, Ca | Cl, NO₃ belongs to the most simple reciprocal systems.

Card 1/2

There are 9 figures, 3 tables, and 10 references, 10 of which

Reciprocal System of Nitrates and Chlorides of Sodium and Calcium

SOV/78-3-8-31/48

are Soviet.

ASSOCIATION: Rostovskiy-na-Donu gosudarstvennyy universitet i Luganskiy gosudarstvennyy nedagogicheskiy institut (State University Rostov na Domu and the State Pedagogical Institute, Lugansk)

SUBMITTED:

July 21, 1957

Card 2/2

1800

21011 S/080/61/034/006/014/020 D247/D305

AUTHOR 8

Kayalova, S.S.

TITLE:

The coating of molybdenum with various silicate fusions

PERIODICAL: Zhrunal prikladnoy khimii, v. 34, no. 6, 1961,

TEXT: In recent work on the protection of metals from oxidation the protection of molybdenum has proved most difficult since at 5200 molybdenum trioxide as formed which sublimates, thus destroying the metal. Substances containing vitriform bands seemed promising and the aim was to study silicate fusions which would coat the metal successfully. The coating was measured by the resting drop method. An apparatus was made to allow determination of coating in various gaseous media up to 11500. It consisted of a horizontal vacuum stove with a platinum-rhodium heater. The specimen of metal whose surface irregularities varied from 5-7 pm, was placed in the stove with pieces of the glass under investigation. There was a

Card 1/3

24011 \$/080/61/034/006/014/020 D247/D305

The coating of molybdenum ...

vacuum in the stove initially and then an inert gas was introduced. The temperature was raised and the change in shape of the drop observed, the degree of coating being determined either by the contact angle of the drop or the area of fusion spread. For substances giving a good coating the second method was used. The specimen of glass was of uniform volume for comparative purposes. Initial studies were done with silicate fusions with a large content of lead monoxide, due to their low viscosity and surface tension. Results were poor and the addition of various oxides and surfaceacting components had little effect. Further work was done on leadless fusions. Study of the influence of cations of groups 1-11 showed that coating improves with decline in the radius of the cation, i.e. $K \rightarrow Na \rightarrow Li \rightarrow Ba \rightarrow Be$. The most interesting results were given by substances containing T103 and B203 together which form a thin film on the surface of the molybdenum. Substances without these components gave poorer results, though better than with lead. There are 3 figures, 1 table and 10 references: 7 Soviet-bloc

Card 2/3

2401 S/080/61/034/006/014/020 D247/D305

The coating of molybdenum ...

and 3 non-Soviet-bloc. The references to English-language publications read as follows: B. Ellefson, and N. Taylor, J. Am. Cer. Sc. 21, 6, 205, 1938; Michael Humenik, J.K., and William D. Kingery, J. Am. Cer. Soc., 37, 1, 18, 1954.

SUBMITTED: August 30, 1960

Card 3/3

APPEN, A. A. and KAYALOVA, S. S.

"Classification of Oxides According to Their Influence on the Surface Tension of Silicate Melts"

report presented at the Sixth International Congress on Glass, 8-14 Jul 62, Wash., D.C.

Institute for Silicate Chemistry, Leningrad

s/020/62/145/003/009/013 B101/B144

AUTHORS:

Appen, A. A., and Kayalova, S. S.

TITĻE:

Surface tension of alkali silicate melts

PERIODICAL: Akademiya nauk SSSR. Doklady, v. 145, no. 3, 1962, 592-594

TEXT: The surface tension s of Li₂O-SiO₂, Na₂O-SiO₂, and K₂O-SiO₂ melts with an Me₂O content of 16-45 mole% was measured by drop weight determination (A. A. Appen, Optiko-mekhanicheskaya promyshlennost, no. 3, 7 (1936), and the effect of the admixture of a second alkali oxide was studied. and the effect of the admixture of a second alkali oxide was studied. This method is suited to determine the c of melts with a viscosity below this method is suited to determine the c of melts with those of other methods 3000 poise. Its results are in good agreement with those of other methods (C. W. Parmelee, K. C. Lyon, C. G. Harman, Univ. Illinois Bull., 36, 81, (C. W. Parmelee, K. C. Lyon, C. G. Harman, Univ. Illinois Bull., 36, 81, June 6 (1939); L. Shartsis, S. Spinner, J. Res. Nat. Bur. Stand., 46, no.5, June 6 (1939); L. Shartsis, S. Spinner, J. Res. Nat. Bur. Stand., 46, no.5, June 6 (1939); Results obtained for Rb₂O-SiO₂ at 1300°C (first figure being 385 (1951)). Results obtained for Rb₂O-SiO₂ at 1300°C (first figure being 46/At, moles Rb₂O, second figure being 6, erg/cm², third figure being 46/At, erg/cm². °C): 17, 200.1, -0.03; 24, 188.0, -0.045; 40, 146.3, -0.087; and Card 1/2

KAYALOVA, Ye. Ya.

Kayalova, Ye. Ya. - "Complications in births due to narrow pelvis," (Material based on the ten year period, 1936 - 1945 from the maternity hospital im prof. Snegireva), Collection dedicated to the Maternity Hospital im. Snegireva on its 175th anniversary, Leningrad, 1949, p. 137-44

SO: U-4355, 14 August 53, (Letopis 'Zhurnal 'nykh Statey, No. 15, 1949)

2-58-5-12/17

AUTHOR:

Kayan, P., Chief of the Oblast! Statistical Administration

TITLE:

To Devote More Attention to Initial Registration at Kolkhozes

(Usilit' vnimaniye pervichnomu uchëtu v kolkhozakh)

PERIODICAL: Vestnik Statistiki, 1958, Nr 5, pp 77 - 78 (USSR)

ABSTRACT:

In a report, workers of the Statistical Administration of the Vinnitskaya Oblast' pointed to various deficiencies in the initial registration of kolkhoz production and recommended measures for improvement. As a result, district organizations took various measures, such as increasing the book-keeping staff, attaching expert accountants to kolkhozes and convening instructive conferences. Two such conferences were subsequently held, where severe criticisms were expressed towards kolkhoz chiefs who

did not maintain established registration orders.

ASSOCIATION: Statisticheskoye upravleniye Vinnitskoy Oblasti (Statistical

Administration of the Vinnitskaya Oblast)

AVAILABLE: Card 1/1

Library of Congress

KAYAN, P.L., golovnyy red.; KRASNER, Ya., tekhn.red.

[Principal indexes of the development of the economy of Viennitea Province; a statistical manual] Osnovni pokaznyky rozvytku narodnoho Province; a statistical manual pokaznyky rozvytku narodnoho Province; a statis

1. Vinnytskaya oblast'. Statisticheskoye upravleniye. 2. Hachal'nik Statistichnogo upravlinnya Vinnits'koi oblasti (for Kayan) (Vinnitsa Province---Statistics)

```
NAVAKATIKYAN, A.O.; KAYAN-YASNYY, V.V.; IOSEL'SON, S.A.; PEVNYY, S.A.

Some data on the effect of the working day on cardiovascular and neural functions in miners. Fiziol.zhur. (Ukr.) 1 no.4:54-63

J1-Ag '55.

(WORK, effects.

on ECG & nervous system in miners)

(EIECTROCARDIOGRAPHY,

eff. of work in miners)

(NERVOUS SYSTEM, physiology.

eff. of work in miners)

(MINING,

eff. of work on ECG & nervous system in miners)
```

KAYANDER, M.S

Dissertations ABSTRACT:

105-58-5-24/28

For the Degree of Candidate of Technical Sciences.
At the All-Union Scientific Research Institute for Metrology
imeni Mendeleyev (Vsesoyuznyy nauchno-issledovatel'skiy institut
metrologii im. Mendeleyeva)

M.S.Kayander on June 9, 1950 "Studying the Conditions for the Increase of the Accuracy of Electrodynamic Equipments at Higher Frequencies". Official opponents: A.D.Kratirov, Professor, Doctor of Technical Sciences and I.G.Rusakov, Docent, Candidate of Technical Sciences.

A.D.Sokolov on May 7, 1954 "Experience Gathered with Respect to the Control of the Electromagnetic Properties of Dynamo- and Transformer Steel". Official opponents: N.N.Razumovskiy, Professor, Doctor of Technical Sciences and N.G.Chernysheva, Candidate of Technical Sciences.

At the Leningrad Institute of Mining imeni Plekhanov (Leningradskiy gornyy institut im. Plekhanova)
V.S.Belovidov on June 30, 1953 "On the Selection of an Electric

V.S.Belovidov on June 30, 1953 "on the Selection of an Electron Drive for Pit Ventilators". Official Opponents: F.N.Shklyarskiy, Professor and A.V.Rys'yev, Docent, Candidate of Technical Sciences. At the Leningrad Institute for Railroad Engineers imeni Obraztsov (Leningradskiy institut inzhenerov zheleznodorozhnogo transporta

Card 2/4 (Leningradskiy im. Obraztsova):

PERIODICAL: Elektrichestvo, 1958, Nr 5, pp. 91-91 (USSR)

KAYANDER. M.S.

Brrors in ammeters and voltmeters used in electromagnetic and electrodynamic systems operated at higher frequencies. Trudy (MIRA 10:12) VNIIM no.24:8-23 54.

(Ammeter) (Voltmeter)

SOV/112-57-5-11173

Translation from: Referativnyy zhurnal. Elektrotekhnika, 1957, Nr 5, p 232 (USSR)

AUTHOR: Kayander, M. S.

TITLE: Reference Instrument Current Transformer for 50-10,000 cps (Obraztsovyy izmeritel'nyy transformator toka dlya diapazona chastot 50-10 000 gts)

。 《中華》:"如果你的知识是是不是不是不是不是的的的法律是是不是不是不是,但是他们是是这样的,我们是是这个人的人的人,但是是这种的人的人,我们就是我们的人,我们就

PERIODICAL: Tr. Vses. n.-i. in-ta metrologii, 1956, Nr 28, pp 36-49

ABSTRACT: This transformer has been constructed for checking instrument transformers and ammeters used at audio frequencies. All necessary measures for reducing errors have been taken in the transformer design. Calculations and corroborating experiments have shown that within the 50-10,000-cps frequency band and with load resistance of 0.4 ohms or lower, errors do not exceed those permissible for the 0.2 class and are independent of the scheme of connections of primary windings. On the basis of the calculations and experiments, a conclusion is drawn that the above current transformer can be used as a reference transformer for the above frequency band.

R.S.M.

Card 1/1

APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0"

SOV/115-58-6-22/43

AUTHORS:

Gordov, A.N., Brodskiy, A.M., Kayander, M.S., Skragan, A.L.

TITLE:

New Apparatus for Checking Thermo-Technical Devices (Novyye ustanovki dlya poverki teplotekhnicheskikh priborov)

PERIODICAL:

Izmeritel'naya tekhnika, 1958, Nr 6, pp 51-56 (USSR)

ABSTRACT:

The All-Union Scientific Research Institute of Metrology imeni D.I. Mendeleyev has developed special devices for the checking of thermo-technical devices. The apparatus UTT-1 is used for checking thermocouples and resistance thermometers. The circuit diagram is shown in Figure 1. The current may be regulated from 4 to 10 ma. The potentiometer R2-A, which has been developed for this apparatus on the base of the potentiometer R2/1, has 3 measuring limits of 1,500, 150 and 15 mv. The apparatus UVPT-1 is used for checking automatic electronic potentiometers, millivoltmeters, devices operating in rheostat and inductive transducers, etc. The circuit diagram is shown in Figure 2. The apparatus has four measuring circuits. The checking of devices with the newly developed apparatus is simpler and faster due to an

Card 1/2

And a surface months will assess a surface

New Apparatus for Checking Thermo-Technical Devices SOV/115-58-6-22/43

efficient arrangement of measuring elements and the use of

the semi-automatic R2-A potentiometer.

There are 4 diagrams.

ASSOCIATION: Vsesoyuznyy nauchno-issledovatel'skiy institut metrologii im.

D.I. Mendeleyeva (All-Union Scientific Research Institute of

Metrology imeni D.I. Mendeleyev)

Card 2/2

BEZIKOVICH, A.Ya.; ZORIN, D.I.; KAYANDER, M.S.

Frequency errors in wattmeters. Trudy VMIIM no.38:103-109 159. (MIRA 13:4)

P. Carrier	ERSENSA	-		AND EST	The contract of the contract o										•	·····					
	[[,14]]	BOT/4407	of the Electric risted.	Additional Sponsorfus Agency: Manchoc-technichestory obshchestro priborostroital'noy promyshlemosti. Unaisaboys respublikashoys previantys.	demy of Sciences cel Sciences, trochemic, Candi- i, Sh. Zaslawakiy, i. St. Zaslawakiy,	ng in the field of plants, in labora- int laboratories of	ference on the over- ry held in Kirey on natitut elektro-	deig of Sciences yellometroitel'- yro of the Instru-	the development of the automatics of the automatics of	Adertic-measuring effortist (b. E. artherny, in a Adertic and a Adertic and Adertic and Adertic and Adertic and Adertic and Attacting the conference were worter of scientists and Attacting the conference were worter of scientists and adertic Adertic and Adertic and Adertic Adertic and Adertic Adertic and Adertic	Beforences &d-	Lactro- bor demons- ting" capaci-	Prequency Arrors	•	well as	yranio System 62 a parameters of	siza for voit- ion for two	Computation of Voltage Trans- 8) Appropriate to the basis of witch to voltage transformer for etric a voltage of \$60/100	95 megzetic s them with Low coercive e well as high		
			11 Problems	troys obshchs pravleniye.	g Member, Ace tor of Techni ces, Y. F. Fe Zuginer, S. K Houser B. J.	reconel vorki 1 instrument rio messurem	runent industries	ineering, Acquire E	relating to Dodeyev),	(N. N. Ebol ntific remea sentatives o	seationed.	casetion of l ion, the suti of compens	rader, fre	ng apparatus h Institute messurement arison. Err	carrents, secs, secs, sod erro	i to Bleatrod is the option	tey compensations, both Box	egutation of parocies on the basis yolkaja tru-	the reperties of and compare yes groups, recability,	K	
,	e pa programme e e e e e e e e e e e e e e e e e e	PRICE I BOOK EXPLOIMATION	priborostroyaniya (Owra	acy: Reachoo-telhaiche: inskoye respublikanskoyo	starents, Corresponding Ed.), M. I. Levin, Doc fate of Technical Scien- noss, A. F. Gorodoviky, liber; Ed. of Publishin,	tended for technical pe schniques, in electrical er systems and in elect-	Soulet electrical last	itate of Electrical Lag akoya respublikanakoya krainian Bepublia Akia	rectan relating to a figure of the statement of the problems (Iz. 5. Arerbulh, I. E.	cuits (A. fa. Solwator, 'saggrafic seasurements 'saggrafic seasurements Action, along with repre- ibrator' is femingent,	in No personalities are orts.	Intl'alloga, J. (Decembers). Supering Computation of Electro- Grand System laterances. Polag formulas of frequency error computation, the author demon- strates has the introduction in a circuit of "computating" capaci- tance marrily reduce the error component.	A. The , D. L. Joria and M. S. Perrader.	The surface speak of the instrument checking apparatus designed by the THIM (All-thice Schoolffic Research Institute of Machinery and Marbioting) Laboratory of Selectrical measurements on the second of the sethod of the research one All the	al inductation and eddy response characteristi -factor vatineters are	mency Error Companisation lish a method of selectiv	a value for cloud; the action fives a general appearance for water are a frequent error and mandes frequenty consequents for two types of value are. There are 2 references, both fordet.	laring M. I., and A. M. Jumbanisham Error Corputation of Voltage That formers Interested for Operation 8 balled Fractucion The authors present the theorytical data on the basis of which the 100 - 10,000 splate mendicuted referency voltage transformers for the 100 - 10,000 opela frequency range with a voltage of 400/100 to sometime water.	Solite, the matter that the control fainties of magnetic order and the properties of magnetic order amount to the majority and control out by properties of majority and control out by properties of majority majority. Low correct order amounts with both Major and Low properties of majority and low properties with both Major and Low properties with both Major and Low properties.	TO DESCRIPTION OF STREET	
	and the second s		reprogramment of the Control of the Control of the Control of the Control Institute Control Ins	Mitional Sycheoring Age prographsenosti. Una	Editorial Formula A. D. Matternine, Corresponding Nomber, Acadery of Sciences Correlations SSS (1989). Ed.) N. L. Levin, Dector of Debatical Sciences Pr. P. Cramstally, Casificity of Technical Sciences, V. P. Netrochado, Guodines, Save of Technical Sciences, V. P. Netrochado, Guodinese et al. R. Matternine, A. P. Correlativity, Engineer, S. Sh. Zanlawity, Engineer, et al. R. Matternine, M. P. Correlativity, Engineer, S. Sh. Zanlawity, Matternia, R. M. Matternia, Phol. Batt. E. M. Matternia, Ph. M.	PURPOSE: This book is intended for technical personnel vorting in the field of shorten assurement techniques, in electrical instrument plants, in laborate backs of electric power quiess and in shorten messurement laboratedes of laters.	OVERAGE: This is a coll all development of the	telbailt As USB (Lost OrrSES) and the Urrain nor preservationnosti (U	ment-maring Industry) whole (reports by A. I Shumbow) were discuss ye terence instruments	electro-measuring cit theory and practice of Attending the confere mission of higher city intrument plants ()	"Chale ht stockyribor" electric power cystem commany ten of the re-	#11'sherm fa M. (be dreamle of the strategy formulae of a strategy formulae of the the to thance strategy reduc	Betlanten & L. L.	the sections speak of the visit	or inductance, sub- matement frequency sated and low priva-	Voltonters To order to establi	a voltmeter circulture meter fraquency err	forers Intended for the entire state of the en	Stol 'te, J. H. Pages The sather exacts outle savertals vo the properties of outle savertals vi	card 6/12	
		-					8		-					* * * * * * *				· · ·			_1
												1		_	5	. 4		DER	<u> </u>	77	

S/194/61/000/008/007/092 D201/D304

AUTHORS:

Bezikovich, A.Ya., Zorin, D.I. and Kayander, M.S.

TITLE:

Frequency errors of wattmeters

PERIODICAL:

Referativnyy zhurnal. Avtomatika i radioelektronika, no. 8, 1961, 10, abstract 8 A65 (V sb. Vopr. obshch. elektropriborostr., Kiye'r, AN USSR, 1960, 53-61)

TEXT:

A method and equipment has been designed at the VNIM im. D.I. Mendeleyev for calibrating ammeters, volt and watt-meters at the frequency range of up to 20,000 c/s. The designed equipment is based on the thermo-electrical comparison method. The calibration accuracy of a.c. at frequencies up to 20,000 c/s is about 0.1 to 0.2%. The instruments produced for mains frequencies have been tested over a wide range of frequencies and for some types additional frequency correction have been determined. Formulae are given of frequency error terms resulting from inductance, mutual inductance and eddy currents. Calibrating frequency curves are

Card 1/2

Frequency errors of wattmeters

S/194/61/000/008/007/092 D201/D304

given for several types of instruments. Some types of wattmeters, designed for 50 c/s operation, may be used at up to 500 c/s provided that additional errors do not exceed the value expressing the class of accuracy of the instrument. Recommendations are given on the means of decreasing the frequency errors of small power factor wattmeters.

Abstracter's note: Complete translation

Card 2/2

S/115/61/000/002/005/006 B116/B203

AUTHOR:

Kayander, M. S.

TITLE:

Differential apparatus for the checking of radiation

pyrometers

PERIODICAL:

Izmeritel'naya tekhnika, no. 2, 1961, 23-26

TEXT: The YPN-4 (URP-4) apparatus which is mostly used in the USSR for the calibrating and checking of radiation pyrometers involves very tiresome work; only one standard pyrometer, or four working pyrometers, can be checked during one shift. The author presents a differential method for the checking of radiation pyrometers. The pyrometers to be checked are not gauged one by one as in the apparatus mentioned at the beginning, but simultaneously placed on either side of the light source in such a position that the radiant flux striking them is identical. The difference between the thermo-emf of the pyrometer to be checked and that of the standard pyrometer is directly measured. The circuits of the two pyrometers are connected in a differential circuit. Fig.1 shows the basic circuit diagram of the apparatus. From the light source 3, the light flux passes through Card 1/3

APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0"

4

Differential apparatus for ...

S/115/61/000/002/005/006 B116/B203

equal condenser lenses K to the object lenses of the two pyrometers. The two circuits are connected to switch 5; the latter connects them with a d.c. potentiometer. This method simplifies the checking, and avoids the influence of voltage instability (of the light source) on the results of the measurement. A УРД (URD) experimental apparatus was built at the VNIIM according to a design by the design engineers L. S. Levin and L. A. Turchaninova; it was adjusted by the mechanicians A. D. Demkin and L. S. Smirnov. In the center of the apparatus, there is a revolving block of the radiator. It carries a cinema projection lamp which sends the radiant flux through two condenser lenses (attached to bows of the block side-walls) to the object lenses of the two pyrometers. The block can be turned through exactly 180°. The condenser lenses can be shifted along the optical axis of the apparatus. Pyrometers of the VNIIM of the TEPA-50 (TERA-50) and PN (RP) types were checked by this experimental apparatus. The calibration curves obtained differed from those on the "black body" by an average of $\pm 4^{\circ}$ C. 65 standard radiation pyrometers were calibrated on the same apparatus. Deviation from the average was 5°C at most. With the use of the "Tara" method (Ref. 1) the checking capacity increased by the 10-fold. The principal shortcoming of the URP-4 apparatus (irregularity

Card 2/3

"APPROVED FOR RELEASE: 06/13/2000

CIA-RDP86-00513R000721220007-0

Differential apparatus for...

8/115/61/000/002/005/006
B116/B203

and imperfect blackness) has not been eliminated in the URD apparatus either. Therefore, the telescopes to be checked must be of the same type and mounted under equal conditions. At present, all instruments arriving at the VNIIM are checked on the URD apparatus. There are 2 figures and 1 Soviet-bloc reference.

Legend to Fig.1: 1) Standard pyrometer, 2) condenser lens, 3) light source, 4) pyrometer to be checked, 5) switch, 6) to the potentiometer.

Fig. 1

Card 3/5

S/263/62/000/013/009/015

1007/1207

AUTHORS:

Gordov, A. N., Zaborovskaya, Z. U., Kayander, M. S.

TITLE:

Apparatus for determining dynamic errors in thermal detectors in temperature measure-

ments under varying heat-transfer conditions

PERIODICAL:

Referativnyy zhurnal, otdel'nyy vypusk. 32. Izmeritel'naya tekhnika, no. 13, 1962, 53, abs-

tract 32.13.390. (Tr. in-tov Kom-ta stabdartov, mer i izmerit. priborov pri Sov. Min.

SSSR, no. 51 (111), 1961, 185-197)

TEXT: A description is given of test units for determining the errors in measurement of temperature fluctuations of a gas stream by different thermal detectors under varying flow-velocity (and heat-transfer) conditions. One of these test units was used to investigate thermal detectors under conditions of monotone variation of flow temperature and velocity. The temperature of a body immersed in the stream was found to vary according to a law basically different from the law of flow-temperature fluctuations. The other unit was used for similar investigations but with fluctuating flow temperature and velocity. A difference was found between the average temperature-fluctuation level of the thermal detector and that of the stream. Experimental methods are described and basic mathematical relationships are given. There are 8 figures and 4 references.

[Abstracter's note: Complete translation.]

Card 1/1

s/589/61/000/051/007/008 1054/1254

AUTHORS:

Gordov, A.N., Zaborovskaya, Z.U., Kayander, M.S.

TITLE:

Experimental installation for determining dynamic errors during temperature measurements at transient heat flux conditions

SOURCE:

USSR. Komitet standartov, mer i izmeritelnykh priborov. Trudy institutov Komiteta. no. 51. (111). 1961. Isledovaniya v oblasti temperaturnykh izmereniy. 185-197

TEXT: A special testing installation was built at VNIIM. One rig was used with continuously changing flow rates and temperatures, and another for a pulsating flow. The following three main sources of errors are discussed:

1) thermal inertia of the sensing element and mechanical inertia of the indicating instruments; 2) design of the sensing elements and heat losses through its connections; 3) faulty measurements of heat transfer coefficients due to inconsistent readings of the thermoanemometer. The frequency range of the pulsations was between 0.1 to 1.0 kcps. There are 8 figures.

ASSOCIATION: VNIIM

SUBMITTED: November 11, 1959

Card 1/1

KAYANDER, M. S.

Radiator with a high sighting ratio for calibrating radiation pyrometers. Ism. tekh. no.10:36-37 0 162.

(MIRA 15:10)

(Pyrometers) (Calibration)

KAYANDER, M.S.

Simulation of the measurement of variable temperatures. Trudy inst. Kom. stand.mer i izm. prib. no.71:198-207 '63.

(MIRA 17:9)

1. Vsesoyuznyy nauchno-issledovatel'skiy institut metrologii im. D.I. Mendeleyeva.

Frequency characteristics of an electronic potentiometer. Izm.tekh. no.2:17-19 F '64. (MERA 17:4)

KAYANDER, M.S.

Dynamic errors 'n measuring variable temperatures by a thermoelectric measuring set. Nov. nauch.-issl. rab. po metr. VNIIM no.3:24-27 164 (MIRA 18:2)

KAYANOVICH, V.A.; KOZHEVNIKOVA, Z.I.; MIROPOLISKAYA, I.L.; MIKHAYLOVA, N.P.; FADRYEVA, A.I.; FOMICHEVA, D.H. (Gor'kiy)

Industrial hygiene and the health of women working with benzene.

Gig. trude i prof. zab. 2 no.1:26-31 Ja-F 158. (MIRA 11:3)

l. Insitut gigiyeny truda i profzaboelvaniy i Meditsinskiy institut.
(BENZENE-TOXICOLOGY)
(IACTATION)

KAYANOVICH, V. A.; KAVALEROVA, S. M.; TROITSKIY, S. A. (Gor'kiy)

Problems in industrial hygiene and the state of health of workers in benzoyl peroxide production. Gig. truda i prof. zab. no.1: 46-49 '62. (MIRA 15:2)

1. Gor'kovskiy nauchno-issledovatel'skiy institut gigiyeny truda i profbolezney.

(INDUSTRIAL HYGIENE) (BENZOYL PEROXIDE_TOXICOLOGY)

KAYASHEV, A.V., insh.

Efficiency of large consolidate transportation units. Zhel, dor.transp. 44 no.3:72-75 Mr '62. (MIRA 15:3)

(Railroads, Industrial)

KAYASHEV, A.V., inzh.

Technical and economic efficiency of the routing of shipper's special destination trains from the loading point. Vest.TSNII MPS 21 no.8:30-34 '62. (MIRA 16:1)

1. Institut kompleksnykh transportnykh problem.
(Railroads—Making up trains)
(Railroads—Freight)

KAYASHEV, T.T.

Attachment to the PS-10 drive for the automatic switching off of the lubricant release. Transp. i khran. nefti 1 nefteprod. no.10:31-32 164. (MIRA 17:12)

1. Severo-Zapadnoye nefteprovodnoye upravleniye.

"APPROVED FOR RELEASE: 06/13/2000 C

CIA-RDP86-00513R000721220007-0

L 46577-66

ACC NR. AR6016246

SOURCE CODE: UR/0058/65/000/011/H016/H016

AUTHORS: Eydukyavichyus, G.; Kayatskas, A.

2 3

TITLE: Some problems in the application of "optimal bases" for the construction of

self organizing systems

SOURCE: Ref. zh. Fizika, Abs. 11Zh121

REF SOURCE: Tr. uchebn. in-tov svyazi. M-vo svyazi SSSR, vyp. 24, 1965, 33-38

TOPIC TAGS: optimal automatic control, self adaptive control, interference immunity

ABSTRACT: The authors consider questions involved in the analysis of noise with the aid of optimal bases, as applied to a self-organizing communication system. Results are presented of experiments on the determination of the interference immunity of signals of various forms when received by an ideal receiver and based on analysis of the noise. The results of the experiments confirm that the optimal bases can find application in self-organizing communication systems. [Translation of abstract]

SUB CODE: 17, 409/

Cord 1/1 hs

"APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0

AUTHOR: Kayatskas, A. (K.Naumestis)

SOV-107-58-4-26/57

TITLE: A Use for Burnt-out Phanotrons (Ispol'zovaniye peregorev-shikh gazotronov)

PERIODICAL: Radio, 1958, Nr 4, p 20 (USSR)

ABSTRACT: A burnt-out phanotron can be used instead of a gas-discharge stabilitron. The author used a VG-176 phanotron for stabilizing 140 v.

1. Voltage stabilizers—Equipment 2. Phanotrons—Applications

Card 1/1

"APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0

KHYHUH, Z. I.

14-57-6-12646 Translation from: Referativnyy zhurnal, Geografiya, 1957, Nr 6,

p 126 (USSR)

AUTHOR:

Kayava, L. I.

TITLE:

A New Type of Nematode (Metastrongylus tschiauricus, n. sp.) in Georgian Wild Boar /Novyy vid nematody (Metastrongylus tschiauricus, n. sp.) dikoy svin'i iz

Gruzii/

PERIODICAL:

Soobshch. AN GruzSSR, 1956, Vol 17, Nr 6, pp 527-530

ABSTRACT:


A new type of nematode (Metastrongylus tschiauricus, n. sp.) has been found in the lungs of the wild boar (Sus scrofa L.) which lives in the Chiaurskiye lesa (forests), Lagodekhi rayon of Georgia. Of the rour other species of this type of swine parasite, one is encountered in Kazakhstan, and three are widely spread

all over the USSR.

Card 1/1

I. Ya.

"APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0



KAYBANOV, Aleksandr Stepanovich; SMAGORINSKIY, B.S., red.; IZHBOLDINA, S.I., tekhn.red.

[Handbook on photography] Fotograficheskii spravochnik. Stalingrad, Stalingradskoe knizhnoe izd-vo, 1961. 127 p. (Photography)

	KA	y B	<u>10</u>	HEU,	-A.	4											***************************************			!					-
		afbow,					10	R	R	*	ø	8	\$	յ ե	Þ	đ	5	8	ğ	Ę	â	ğ	Ý E	133	
	į,	Mitherial Bord: Hab, Vatolia (Seep. M.), Cambinabe of Scalmids Sciences) Ads. Milhiladity, Professor, Booker; V.In. Milher, Professor; PL. Paul Cambides of Trebacted Sciences; and H.A. Lingel, Cambides of Trebacted Sciences; M.: M.S. Burmarraique.	į	its of investigations of theoretical pro- try and gives infinitelying the efficient ty and prime infinitelying and on the de- cesses in the artificialities and chemical vertices by plantar ensuings and experienced the property of the artificial conference of the c	tist.	rties of	4		Tanker .		A a a a a a a a a a a a a a a a a a a a	tes for	4 Sot	1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	F 4	8,	ive Date oftel One	odife.	sting of	ton and	ž Ž		Tokaray, <u>Alls,</u> nod gios SpansidyIorestigation of the Copolymers of Poly-1,3 balyfena Oprol Pranints nod Styrene	ylation	
-		1	realizerglete.	of theoretical pro- tion on the efficie theory and on the de surficel and charical mars and experience of Metallurer.	rical B	Tapor	- i	9000 M	er Selfidos of Bishal	9	dors to	requirer ride Se	of Relocates VIIIa Soli	e the Lecuting Sol	115 Bot (a)	Condition.		wior of		Compost:	Thoughorns .		gers of	14 AU	
T T	e, 1990, 157 p. B	100	1	for the control of th	A 11 4	1	ofer of desents	4		ALL CAN	100	53		a B	A L	73	84 9 9	the Behavior	por Se	Tadour 1		7	e Capoli,	e Cara	
titut metallurgii	A 4, 250			day and a		1		Į	1 1	ation of Despition	1	1112		Option Confiction		Etc. to	2	Pr. O	be melter	Change in Chesteril ting	1	ine Reguld	8 8 \$	of Isop	
Ä	24	3	1	is the section of the second section of the section se	12	11	1	1	Ordensies .	Polenta			à			(Landa	E	1	8	P. C.	4 4.30	rotite	etigatio	duct lea	
Ural'stiy fillst.	2 (1 1) D	Const.	134	detry med r	1 32	. 64		# 8 8			100		TOOMS	Tooler.	desembles or Charl	A Property	100	Told La	obrowkis	Opone Copola		a of Per	fe Inve	- Pro	
al ratedy	(Trussections of the last Sciences, UESR, No. 4) for ted., 1,000 copies pristed.	foods.	This book is intended for force	MAME: The book presents results of ter- blame is setalling; and chemistry and give use of nor materials in Strongs and soulf we do not not product on processes in signaturies. The criticism way written by	Chemistry, and Electrochemistry, Deal Research, Assessey of Sciences Shawria, S.V., E.V., Sapontatiores, and B.W. Leptentials. Electrical Read Press Composition of Eriquetical Limits Section (No. 1994).	Theory, fig., and ye.A. Vetropic, On the Commertion Before the Vegorization of \$6115s and the Pressure of Saturated V	Browler, Y.L., and E.P. Diyer (D. Brewfile, Concentration	Reinel and Otherst	Starbor, L.K., and R.L. Enthure. and Others	Contrayer, L.Ya., and R.V. Bairner, knotes in Punci Chlorides	Denosias, k.K., f.K. Marting, and P.A. Paskelber. Immerigation of Conditions for Electrodeposition of Copyer From Ballace Schoolson in Presence of Irus, Electrode Codeins Cations and the Matrice Anion	Prighers, L.K., ^b r.d., Productor, and L.K. Charilan. Sens Frenquisties for No Restricts Production of Les hymps from Abulian Alarida Saintions and Balestian of Institute Anales for Restrativals	Spatemather, 6.3. Some Permitserities of the Se mai the litting the Statemate Process	빏	Mikalingity, Aug., and G.B. Botherdiov. Predection of Netalife Sodims Tarbon Sebuction of the Sulfate or Carbonate (Englormoury Texts)	<u>mining 7.7., 70-1. Verymin, 1.4. Tinicanio, sed A.A. Intellina.</u> The Froblem of Pasings of Zize from [Coppes] Matte to the Gassess Fa Maria Air Eiset	Byrg. L.L., S.A. Ispanicher, and J.P. Diyer (Document). One on the Carring of Liquid Into the Cos-examin's follow in Ary- worter	htthmylov, V.V., Z.C., Radinov, and V.I., Includov. On the B of Borou laring the Metallingical Treatment of Boronia Ores	Laybishor, A.Y., and V.P.T. Chemodrovkin. On the Belting and Overn P.F. Took in Dis Carolis	Laylings A.V., and V.P. Chernobrovin. Chernical Content of Pig Iron Daring Oppola Melilan	Dermobrowith, V.P., A.A. Dolyrden's and V.J. Belyconte.	On the Deposition of Perrotitasium	Dought 3t	Piotizin, M.I., and V.G. Plynamin, Production of Imoparatitus by Alsylation of Imoparatitus by Alsylation	
	franct denos,	A CAN	ook te 1	Linery Learling Pre-pro-	T. Bept	100	1de Con	i i	Ţ	in the	A STATE OF		See Sta		100	Total	or Liqu	22°2 E	Curole	Fig Iron	Fig. A.A.	a the De	od D.S.	end V.G.	
milys sent MINE.	- L	Chultan Set at	The b	To the second	Compo	L., C.	1	00	1	T, E.Yo.		Anital a	or, o.	Eute Eute	Str. B.	markirer, T.P., the Problem of P Bering Air Hast	arrylag		,	to the	wite, V		Arke T	ALL SON	
Ì	1		TOTAL STREET	To a series			errefor.				No ditte	F/2 7				The same	100	f Porce	aybi elle	of Con	ndomina is milas	Pitner, Tu.L.	utylen.	otrica,	
٩,	•	•	£	ъ.		· •		•	•	-/-		-			-		700	40	7	-	¥.	~1	Z4,48	6 6	
	· Project		1			1		क्षात्त्व -	migration i	CEPTER :	A			-		ښتهنيار	, ,			 					
					:											1									

KAYBICHEV, A.V., kand. tekhn. nauk

Angular measurement of the amount of metal in barreltype and teapot spout ladles. Lit. proizv. no.11:37-38 N '65. (MIRA 18:12)

KAYBICHEV. A.V.; CHERNOBROVKIN, V.P.

Melting and overheating of cast iron in cupola furnaces. Trudy Inst. met. UFAN SSSR no.4:101-106 158.

(MIRA 12:10)

(Cupola furnaces) (Cast iron)

KAYBICHEV, A.V.; CHERNOBROVKIN, V.P.

Change in the chemical compostion and heat capacity of cast iron during its melting in cupolas. Trudy Inst. met. UFAN SSSR no.4:107-111 '58. (MIRA 12:10) (Cupola furnaces)

CHERNOBROVKIN, V.P.; ANAN'IN, A.A.; DOBRYDEN', A.A.; KAYBICHEV, A.V.

Comparative evaluation of foundry irons of the Ural plants. Lit. proizv. nc. 5:8-10 My '61. (MIRA 14:5) (Cast iron) (Ural Mountains—Metallurgical plants)

KAYBICHEV, A.V.; CHERNOBROVKIN, V.P.

Lower boundary of the melting zone in cupola furnaces. Lit. proizv. no.2:17 F '63. (MIRA 16:3)

CHERNOBROVKIN, V.P.; ANAN'IN, A.A.; KAYBICHEV, A.V.; DOBRYDEN:, A.A.

Gases in foundry iron. Izv. vys. ucheb. zav.; chern.met. 5 no.4: (MIRA 15:5)

1. Ural'skiy filial AN SSSR. (Gases in metals)

"APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0

KAYBICHEV, A.V.; CHERNOBROVKIN, V.P.

Calculating the overheating of cast iron and position of the melting zone in cupolas. Izv. vys. ucheb. zav.; chern. met. 5 no.10:137-148 '62. (MIRA 15:11)

1. Institut metallurgii Ural'skogo filiala AN SSSR. (Cupola furnaces) (Heat-Transmission)

CHERNOBROWKIN, V.P.; KAYBICHEV, A.V.; ANAN'IN, A.A.

Effect of gas removal from cast iron on the structure and form of graphite. Izv. vys. ucheb. zav.; chern. met. 6 no.4: 136-140 '63. (MIRA 16:5)

1. Ural'skiy filial AN SSSR. (Gases in metals)

(Cast iron-Metallography)

18.5000

75577 sov/130-59-10-9/20

AUTHOR:

Magnesia Lining Material With Sintering Additions Kaybicheva, M. N. Metallurg, 1959, Nr 10, pp 17-18 (USSR)

TITLE:

PERIODICAL:

ABSTRACT:

In the search for better linings for induction furnaces a magnesia mass with ferrous and ferrotitanium additions was tested in a crucible. The chemical composition is shown in Table 1. Based on experimental work the author makes the Based on experimental work the author makes the following recommendations: (1) metallurgical following recommendations: (1) metallurgical expenses the following recommendations material for crucible material for crucible powder "Ekstra" as basic material for crucible following brick after in steel-melting furnaces for melting of use in steel-melting furnaces for melting mixtures chromium steel, (3) any of the following mixtures chromium steel, (3) any of the following mixtures as sintering additions, (a) magnesite - slag - titanium-magnetite concentrate (2.5:2.5:1), (b) as sintering additions, (a) produce dicalcium ferrite raw dolomite - scale to produce dicalcium ferrite and, (c) magnesite and titanium-magnetite concentrate (4:1), (4) Grain composition of the charge-

card 1/4

APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0" Magnesia Lining Material With Sintering S0V/130-59-10-9/20 Additions

- 2 to 4 mm fractions: 45 to 50%, 0.088 to 2 mm: 15%, and under 0.088 mm: 35 to 40%, (5) light-weight crucible lid and decreased water supply to inductor after tapping so as to protect lining from drastic temperature changes. The use of magnesia material with sintering additions doubles or triples lining life of induction furnaces. There is I table.

Creek In		Change Composition	Chemical Composition, %												
	1 6 6 E		sio,	AI,O,	710,	Fe _a O _a	PeO	CaO	MgO	Cr.0.	MnO	n. n. n			
40	30	Magnesite powder "MPM" (Fractions O to 4 mm): 402 Combined ground magnesite. 1	4,10	3,03	0,56	0,79	0.97	4,63	82,95	_	0,56	-			
50	40	(45%), open-hearth stag (45%), ilmanita (10%): 10% Ekstra magnasita powder: 90%, combined ground magnasita claetria furnace stag and ilmanita (2.5;2.5;1.0):	4,17	0,52	0,45	4,88	_	4.29	85,85		-	6,13			
50	50 — 6 0	10%	2.00	0.07	3,20	2,33	_	3,26	82,52	-	-	3,70			
4 0	30	"Ekstre" magnesite powden: 9070, ground raw dalomite - scale mixture: 1070	3,52	1.46	not daterminad	2,84	3,19	5,72	83.70			0,044			
00	60—70	Chrome-magnesite: 100%	3,40	6.52	·	9,29	1,22	1,25	62,99	14,20	0.23	_			

Magnesia Lining Material with Sintering Additions

SOV/130-59-10-9/20

ASSOCIATION: Eastern Institute of Refractories (Vostochnyy institut

ogneuporov)

Card 4/4

APPROVED FOR RELEASE: 06/13/2000 CIA-RDP86-00513R000721220007-0"

KAYBICHEVA, M. N.; FADEYEVA, N. I.; Prinimali uchastiye: KOSOLAPOV, Ye. F.; GILEV, Yu. P.; DRESVYANKIN, V. I.; MIKHAYLOV, V. S.

Studying conditions of service and the character of roof failure in electric steel smelting furnaces. Trudy Vost. inst. ogneup. no.2:101-117 '60. (MIRA 16:1)

(Electric furnaces—Maintenance and repair) (Refractory materials—Testing)

S/131/60/000/04/10/015 B015/B008

AUTHORS:

Kaybicheva, M.N., Tulin, N.A., Bastrikov, N.F., Fadeyeva, N.I.

TITLE:

Wall-blocks of Electric Steel-melting Furnaces From Scrap of

Magnesite-chromite Bricks

PERIODICAL: Ogneupory, 1960, No. 4, pp. 186-188

TEXT: Experiments with these wall-blocks which were carried out at the Chelyabinskiy metallurgicheskiy zavod (Chelyabinsk Metallurgical Plant) are described in the paper under review. The charge was produced by crushing scrap of used magnesite-chromite- and chrome-magnesite bricks. The chemical composition of the experimental charges is given in table 1 and their granulation in table 2. Various grades of steel were smelted in the furnace with magnesite-chromite wall-blocks, the temperature of the metal before tapping being between 1560 and 1640°. It is stated in conclusion that the stability of the magnesite-chromite wall-blocks rammed from scrap is not inferior to that of wall-blocks made from magnesite powder. Various other furnace parts can also be produced from ground scrap of used bricks. The consumption of metallurgical

Card 1/2

Wall-blocks of Electric Steel-melting Furnaces From Scrap of Magnesite-chromite Bricks S/131/60/000/04/10/015 B015/B008

magnesite powder may be reduced by using scrap. There are 2 tables.

Card 2/2

KAYBICHEVA, M.N.

Dust formation in electric furnaces in accelerating the metallurgical process by oxygen. Stal' 20 no.9:809-812 S '69. (MIRA 13:9) (Electric furnaces) (Oxygen--Industrial applications)

KAYBICHEVA, M.N., TULIN, N.A., BASTRIKOV, N.F., FEDEYEVA, N.I.

Wall blocks of electric steel-smelting furnaces made of magnesite-chromite brick wastes. Ogneupory 25 no.4:186-188 '60. (MIRA 13:8) (Firebrick-Testing) (Chelyabinsk--Smelting furnaces)

MAMYKIN, P.S.; KAYBICHEVA, M.N.

Manufacture and performance of crucibles of induction furnaces made of magnesite with sintering additives. Ogneupory 25 no.7:308-312 160. (MIRA 13:8)

1. Vostochnyy institut ogneuporov. (Crucibles)

BARIN, Stepan Yakovlevich; KAYBICHEVA, M.N., inzh., retsenzent; DOVGOPOL, V.I., inzh., red.; DUGINA, N.A., tekhn. red.

[Advice to the steelmaker] Sovety staleplavil'shchiku. Moskva, Mashgiz, 1961. 37 p. (Biblioteka racochego-mashinestroitelia. Seriia: Peredovaia tekhnika - osnova kommunisticheskogo truda, no.4) (MIRA 15:6) (Steel-Electrometallurgy) (Smelting furnaces)